



# CITY OF BISHOP

377 West Line Street - Bishop, California 93514  
Post Office Box 1236 - Bishop, California 93515  
760-873-8458 publicworks@ca-bishop.us  
www.ca-bishop.us

## Addendum 4

**30 October 2014**

### **Warren Street Improvement Project**

This addendum changes the 2 October 2014 Bidding Information and Contract Documents for this project.

1. Replace the provision for Landscape Boulder with the following:

"Landscape Boulder shall be of native rock, granite or volcanic tuff, with no more than 20% of the total being volcanic tuff. Landscape Boulder shall not have any visible marks from lifting or placing equipment. Landscape Boulder will be designated by nominal size and shall conform to the following gradation:

<b>PERCENT OF BOULDERS</b>	<b>SIZE</b>
40%	2-ton
25%	1-ton
15%	Half-ton
10%	Quarter-ton
10%	250-lb

Landscape Boulder shall be placed as directed by the Engineer with about 40% of each boulder buried and shall be measured actual."

2. Add the following provision to the end of Section Bid Items, of the Special Provisions:

"29. Large Landscape Boulder: Large Landscape Boulder shall be of native rock, granite or volcanic tuff, with no more than 20% of the total being volcanic tuff. Large Landscape Boulder shall have a minimum of visible marks from lifting or placing equipment. Large Landscape Boulder will be designated by nominal size and shall conform to the following gradation:

<b>PERCENT OF LARGE BOULDERS</b>	<b>SIZE</b>
20%	25-ton
30%	10-ton
50%	5-ton

Large Landscape Boulder shall be placed as directed by the Engineer with about 40% of each boulder buried and shall be measured actual."

3. Replace pages 5, 6, and 7 of 35 of the Bid Form with the attached pages. The attached pages reflect changes 1 and 2 of this addendum.



David Grah  
Director of Public Works

**Bid Form: Option 1**

**Storm drain improvements: 50+03 on, excluding inlet at 50+72 left.**

**Street improvements: Warren Street 11+44 to 20+58 and all Church Street, Academy Avenue, and Pine Street improvements.**

Item	Quantity	Unit	Description	Unit Price	Total Item Price
1	1	LS	Mobilization		
2	1	LS	Erosion Control		
3	1	LS	Traffic Control		
4	9	EA	Remove Tree		
5	170	LF	6" and 8" Storm Drain Line		
6	503	LF	12" Storm Drain Line		
7	1286	LF	18" Storm Drain Line		
8	16	EA	Curb Inlet		
9	1	EA	Stormwater Separator		
10	2	EA	Manhole		
11	20735	SF	Sidewalk		
12	2472	LF	Curb (A2-6)		
13	2270	LF	Curb (A1-6)		
14	13	EA	Curb Ramp		
15	5588	SF	Roadway Concrete		
16	4955	SF	Driveway		
17	4	EA	Area Drain		
18	60	EA	Tree		
19	18	EA	Tree Grate		
20	20	EA	Landscape Boulder		
21	3	EA	Concrete Feature		
22	29	EA	Street Light		
23	1	LS	Irrigation System		
24	1426	CY	Cement Treated Base		
25	1263	TON	Hot Mix Asphalt		
26	108	SF	Pavement Marking		
27	1,580	LF	Pavement Stripe		
28	16	EA	Utility Cover		
29	10	EA	Large Landscape Boulder		
				<b>Total Bid</b>	

**CY is cubic yard; EA is each; LF is linear foot; LS is lump sum; SF is square foot**

**Bid Form: Option 2**

**Storm drain improvements: 50+03 on, excluding inlet at 50+72 left.**

**Street improvements as follows: Warren Street 11+44 to 19+75 and all Church Street and Academy Avenue improvements.**

Item	Quantity	Unit	Description	Unit Price	Total Item Price
1	1	LS	Mobilization		
2	1	LS	Erosion Control		
3	1	LS	Traffic Control		
4	9	EA	Remove Tree		
5	170	LF	6" and 8" Storm Drain Line		
6	503	LF	12" Storm Drain Line		
7	1286	LF	18" Storm Drain Line		
8	16	EA	Curb Inlet		
9	1	EA	Stormwater Separator		
10	2	EA	Manhole		
11	17210	SF	Sidewalk		
12	1797	LF	Curb (A2-6)		
13	2007	LF	Curb (A1-6)		
14	9	EA	Curb Ramp		
15	4210	SF	Roadway Concrete		
16	3564	SF	Driveway		
17	4	EA	Area Drain		
18	52	EA	Tree		
19	18	EA	Tree Grate		
20	20	EA	Landscape Boulder		
21	3	EA	Concrete Feature		
22	22	EA	Street Light		
23	1	LS	Irrigation System		
24	1159	CY	Cement Treated Base		
25	1026	TON	Hot Mix Asphalt		
26	68	SF	Pavement Marking		
27	1,580	LF	Pavement Stripe		
28	12	EA	Utility Cover		
29	10	EA	Large Landscape Boulder		
				<b>Total Bid</b>	

**CY is cubic yard; EA is each; LF is linear foot; LS is lump sum; SF is square foot**

**Bid Form: Option 3**

**Storm drain improvements: 50+03 on, excluding inlet at 50+72 left.**

**Street improvements as follows: Warren Street 11+44 to 17+85 and all Church Street and Academy Avenue improvements.**

Item	Quantity	Unit	Description	Unit Price	Total Item Price
1	1	LS	Mobilization		
2	1	LS	Erosion Control		
3	1	LS	Traffic Control		
4	7	EA	Remove Tree		
5	170	LF	6" and 8" Storm Drain Line		
6	503	LF	12" Storm Drain Line		
7	1286	LF	18" Storm Drain Line		
8	16	EA	Curb Inlet		
9	1	EA	Stormwater Separator		
10	2	EA	Manhole		
11	14515	SF	Sidewalk		
12	1445	LF	Curb (A2-6)		
13	2007	LF	Curb (A1-6)		
14	9	EA	Curb Ramp		
15	4210	SF	Roadway Concrete		
16	2750	SF	Driveway		
17	4	EA	Area Drain		
18	44	EA	Tree		
19	10	EA	Tree Grate		
20	20	EA	Landscape Boulder		
21	3	EA	Concrete Feature		
22	20	EA	Street Light		
23	1	LS	Irrigation System		
24	998	CY	Cement Treated Base		
25	884	TON	Hot Mix Asphalt		
26	68	SF	Pavement Marking		
27	1,580	LF	Pavement Stripe		
28	12	EA	Utility Cover		
29	10	EA	Large Landscape Boulder		
				<b>Total Bid</b>	

**CY is cubic yard; EA is each; LF is linear foot; LS is lump sum; SF is square foot**